Bruhath Bengalore Mahanagara Palike

Name of Work: Asphalting to roads at Defence Colony and surrounding areas in Ward No.14 Begalagunte

Modified Schedule-B

Sl No	Description of Work	Unit	Qty	Rate
1	Removing and refixing stone slabs of drains and Pointing in CM (1:3)	Sqm	531.00	116.87
	Upto 125%	Sqm	132.75	116.87
	Above 125%	Sqm	6251.42	116.87
2	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter	Cum	1840.92	247.55
	Upto 125%	Cum	460.23	247.55
	Above 125%	Cum	2204.30	236.60
3	Providing & laying RCC Drain Slab of 100mm (DATA RATE)	Sqm	1728.79	2318.40
4	KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	9917.30	5.57
	Upto 125%	Sqm	2479.33	5.57
	Above 125%	Sqm	9834.12	5.56
5	Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406	Cum	944.47	2101.34
	Upto 125%	Cum	236.12	2101.34
	Above 125%	Cum	807.52	2101.34
6	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WBM, WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH Specification No. 502	Sqm	4106.40	31.16
	Upto 125%	Sqm	1026.60	31.16
	Above 125%	Sqm	3510.96	35.61

Scanned with OKEN Scanner

	Description of Work	Unit	Qty	Rate
7	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting thehot mix to worksite, laying to the required grade, level and alignment, rolling with, smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications. MORTH Specification No. 507	Cum	432.20	6690.24
8	KSRRB 500-9. Providing and applying tack coat using 80/100 grade bitumen(VG10) on granular base such as WBM surfaces hot bitumen primed at 4 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH Chapter 5	Sqm	15418.40	13.36
	Upto 125%	Sqm	3854.60	13.36
	Above 125%	Sqm	2957.74	13.35
9	KSRRB M500-19. Providing and laying bituminous concrete 40 mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. MORTH Specification No. 509	Cum	308.37	8656.91
	Upto 125%	Cum	77.09	8656.91
	Above 125%	Cum	503.77	10753.89
10	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803	Sqm	427.75	477.48
	Upto 125%	Sqm	106.94	477.48
	Above 125%	Sqm	569.74	477.43

Contractor

Executive Engineer
Dasrahalli Division
BBMP

Scanned with OKEN Scanner

Bruhath Bengalore Mahanagara Palike

Name of Work: Asphalting to roads at Defence Colony and surrounding areas in Ward No.14 Bagalagunte

Modified Schedule-B

Sl No	Description of Work	Unit	Qty	Rate
1	Removing and refixing stone slabs of drains and Pointing in CM (1:3)	Sqm	531.00	116.87
	Upto 125%	Sqm	132.75	116.87
	Above 125%	Sqm	6251.42	116.87
2	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter	Cum	1840.92	247.55
	Upto 125%	Cum	460.23	247.55
	Above 125%	Cum	2204.30	236.60
3	Providing & laying RCC Drain Slab of 100mm (DATA RATE)	Sqm	1728.79	2318.40
4	KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	9917.30	5.57
	Upto 125%	Sqm	2479.33	5.57
	Above 125%	Sqm	9834.12	5.56
5	Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406	Cum	944.47	2101.34
	Upto 125%	Cum	236.12	2101.34
	Above 125%	Cum	807.52	2101.34
6	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WBM, WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH Specification No. 502	Sqm	4106.40	31.16
	Upto 125%	Sqm	1026.60	31.16
	Above 125%	Sqm	3510.96	35.61

Scanned with OKEN Scanner

No	Description of Work	Unit	Qty	Rate
7	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting thehot mix to worksite, laying to the required grade, level and alignment, rolling with, smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications. MORTH Specification No. 507	Cum	432.20	6690.24
8	KSRRB 500-9. Providing and applying tack coat using 80/100 grade bitumen(VG10) on granular base such as WBM surfaces hot bitumen primed at 4 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH Chapter 5	Sqm	15418.40	13.36
	Upto 125%	Sqm	3854.60	13.36
	Above 125%	Sqm	2957.74	13.35
9	KSRRB M500-19. Providing and laying bituminous concrete 40 mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. MORTH Specification No. 509	Cum	308.37	8656.91
	Upto 125%	Cum	77.09	8656.91
	Above 125%	Cum	503.77	10753.89
10	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803	Sqm	427.75	477.48
	Upto 125%	Sqm	106.94	477.48
	Above 125%	Sqm	569.74	477.43

Contractor

Executive Engineer
Dasrahalli Division
BBMP

Scanned with OKEN Scanner